

PRINCIPAL
LBS INSTITUTE OF TECHNOLOGY FOR WOMEN, POOJAPPURA
THIRUVANANTHAPURAM

QUOTATION NOTICE

No. P/2443/LBSITW/2024

Dated: 17.02.2024

Quotation Number	P/2438/LBSITW/202401.03.2024
Due date and time for receipt of quotations	01.03.2024 11 AM
Date and time for opening of quotations	01.03.2024 11 AM
Designation and address of officer to whom the quotation is to be addressed	PRINCIPAL LBSITW, POOJAPPURA, TRIVANDRUM.
Superscription: Quotation for the Replacing Indian closet with western closet in room No.504 of LBSITW, Poojappura.	

Sealed quotations are invited by the Principal, LBS Institute of Technology for Women, Poojappura, Thiruvananthapuram, Kerala, Pin-695012, for the Replacing Indian closet with western closet in room No.504 of LBSITW, Poojappura of LBSITW, Poojappura as specified in the schedule attached below. The rates quoted should be for executing the work along with materials as specified. The necessary superscription, due date for the receipt of quotations and the name and address of officer to whom the quotation is to be sent are noted above. Any quotation received after the time fixed on the due date is liable to be rejected. The maximum period required for the execution of the work should also be mentioned. The prices quoted should be inclusive of materials, labour and all taxes/ charges etc.

Special conditions if any or printed on quotation notice will not be applicable to the contract unless they are expressly accepted in writing by the undersigned.





PRINCIPAL

ESTIMATE

Name of work : Estimation for replacing indian closet with western closet in room no:504, LBSITW

Sl No.	Specification	No:s	length	Breadth	Height	Quantity	Unit	Rate (Rs)	Amount (Rs)
1	Dismantling tile work in floors or thickness of tiles 10 mm to 18mm and laid in cement mortar including stacking material within 50 metres lead including labour charge.		1.4	1.36		1.90	sqm	70.00	135.00
2	Dismantling of water closet squatting pan (Indian type W.C.pan) including labour charge	1						900.00	900.00
3	Providing and laying water proofing treatment in sunken portion of WCs, bathroom etc., by applying cement slurry mixed with water proofing cement compound consisting of applying : (a) First layer of slurry of cement @ 0.488 kg/sqm mixed with water proofing cement compound @ 0.253 kg/ sqm. This layer will be allowed to air cure for 4 hours. (b) Second layer of slurry of cement @ 0.242 kg/sqm mixed with water proofing cement compound @ 0.126 kg/sqm. This layer will be allowed to air cure for 4 hours followed with water curing for 48 hours. The rate includes preparation of surface, treatment and sealing of all joints, corners, junctions of pipes and masonry with polymer mixed slurry including labour charge,transportation charge and as directed by the engineer in charge.		1.4	1.36		1.90	sqm	516.60	1000.00
4	Providing and laying in position cement concrete of specified grade including the cost of centering & shuttering - All work up to plinth level:1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40 nominal size) including labour charge,transportation charge and as directed by the engineer in charge.		1.4	1.36	0.1	0.19	cum	6500.00	1250.00
5	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., Size of Tile 500x500 mm including labour charge,transportation charge and as directed by the engineer in charge.		1.4	1.36		1.90	sqm	1400.00	2660.00
6	Providing and fixing white vitreous china pedestal type water closet(European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :W.C. pan with ISI marked white solid plastic seat and lid including labour charge,transportation charge and as directed by the engineer in charge.	1						8000.00	8000.00
7	Plumbing fixtures include health faucet with wall hook and 1 m stainless steel braided rubber hose, elbow and 1m pipe including material cost, labour charge and transportation charge as directed by the Engineer in charge.							4000.00	4000.00
Total									17945.00
Contingencies if any									4000.00
GST(18%)									3950.00
Grand Total									26000.00
(Rupees Twenty Six Thousand Only)									




PRINCIPAL
 LBS Institute of Technology for Women
 Porappara
 Thiruvananthapuram-695012