

LBS INSTITUTE OF TECHNOLOGY FOR WOMEN, POOJAPPURA
THIRUVANANTHAPURAM
QUOTATION NOTICE

No. P/1404/LBSITW/2025

Dated: 28.05.2025

Quotation Number	P/1404/LBSITW/2025
Due date and time for receipt of quotations	05.06.2025, 11 AM
Date and time for opening of quotations	05.06.2025, 12 Noon
Designation and address of officer to whom the quotation is to be addressed	PRINCIPAL LBSITW, POOJAPPURA, TRIVANDRUM.
Superscription: Name of Work: Reconstruction of Wall and Providing Steel Door in Third Floor of Main Building LBSITW, Poojappura.	

Sealed quotations are invited by the Principal, LBS Institute of Technology for Women, Poojappura, Thiruvananthapuram, Kerala, Pin-695012, for the repairing of GI roofing on the top of main building of LBSITW, Poojappura as specified in the schedule attached below. The rates quoted should be for executing the repairing work along with materials as specified. The necessary superscription, due date for the receipt of quotations and the name and address of officer to whom the quotation is to be sent are noted above. Any quotation received after the time fixed on the due date is liable to be rejected. The maximum period required for the execution of the work should also be mentioned. The prices quoted should be inclusive of materials, labour, conveyance and all taxes/ charges etc.

Special conditions if any or printed on quotation notice will not be applicable to the contract unless they are expressly accepted in writing by the undersigned.

Name of Work: Reconstruction of Wall and Providing Steel Door in Third Floor of Main Building at the entrance of the new connection bridge between the main building and the seminar hall.

Sl.No:	Price Sl.No:	Specification	Qty.	Rate	Unit	Amount
1	50.6.5.2	Hollow block masonry using pre cast blocks (Factory made) of size 40x20x15cm or nearest available size confirming to IS 2185 part 1 of 1979 for super structure up to floor two level with thickness 15cm in: CM 1:6 (1 cement : 6 coarse sand) etc complete.	0.5	6005.44	Cu.m	3002.72
2	13.4.2	12 mm cement plaster of mix: 1:6 (1 cement : 6 coarse sand)	6	310.23	Sq.m	1861.38
3	10.16.2	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) for Door , including cutting, hoisting, fixing position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Hot finished seamless type tubes	40	185.35	kg	7414.00

4	13.43.1	Applying one coat of water thinnable cement primer of approved brand and manufacture on wall surface: Water thinnable cement primer	6	70.64	Sq.m	423.84
5	13.83.2	wall painting with premium acrylic emulsion paint of interior grade, having VOC (Volatile including applying additional coats wherever required to achieve even shade and colour. Two coats	3	134.1	Sq.m	402.30
6	13.46.1	Finishing walls with Acrylic Smooth exterior paint of required shade: New work. (Two or more coat applied @ 1.67 ltr/10 sqm over and including priming coat of exterior primer applied @ 2.20 kg/10 sqm)	3	193.89	Sq.m	581.67
7	13.62.1	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture .	6	208.54	Sq.m	1251.24
			Total		14937.15	
			GST@18%		2688.6	
			Grand Total		17625.84	
			Say Rs.		18000.00	
(Rupees Eighteen Thousand only)						

Strike out whichever is not applicable
I/We agree to carry out the work

1. At estimate rate
2. At _____% below estimate rate
3. At _____% above estimate rate

Copy to:

- 1) College Website
- 2) Notice Board.



[Signature]
Principal
LBS Institute of Technology
For Women
Thiruvananthapuram